ROYALTY CALCULATION

Name of Work : Construction of RO Plant in Bagalagunte Ward No 14

Job Code:		Est.Cost Rs.	12.50 Lakhs
Plain Cement Concrete 1:3:6			
Description	**Qty in Cum**	**Constant**	**Total Qty**
Sand	29.33	0.465	13.64
Jelly	29.33	0.892	26.16
Cement Concrete M 25			
Sand	6.46	0.43	2.78
Jelly	6.46	0.69	4.46
Plain Cement Concrete 1:2:4			
Sand	2.46	0.46	1.13
Jelly	2.46	0.88	2.16
Size Stone Masonary			
Stone	6.32	1.00	6.32
Sand	6.32	0.45	2.84

Sl	Items	Qty		Rate		Amount
1	Sand	20.39	X	138	=	2814-00
2	Jelly	32.78	X	126	=	4130-00
3	Stone	6.32	X	184	=	1163-00

Note: Only Qty is Given By Sub Division office

Total = 8,107-00

Asst.Engineer

Asst.Executive Engineer
T.Dasarahalli Sub Division

Scanned with CamScanner